HOUSING AUTHORITY OF THE CITY OF FROSTBURG: BATHROOM RENOVATIONS: FINISH LEGEND

DATE: 8/31/2026

GENERAL NOTES

1. CEILING PAINT: FLAT FINISH / NO VOC
2. WALL PAINT: FLAT FINISH / NO VOC
3. TRIM / DOOR PAINT: SEMIGLOSS FINISH / NO VOC
4. ALL ADHESIVES TO BE LOW/NO VOC
5. CONTRACTOR TO INFORM DESIGNER OF ANY DISCREPANCIES IN SCHEDULE BEFORE ANY WORK COMMENCES.
6. CONTRACTOR TO REFER TO INSTALLATION INSTRUCTIONS FOR ALL PROPER INSTALLATION OF MATERIALS.
7. SUBMITTALS OF ALL FINISH PRODUCTS REQUIRED FOR APPROVAL. CONTRACTOR TO SUBMIT ANY RECOMMENDED SUBSITUTIONS FOR ARCHITECTURAL APPROVAL FOR CONSIDERATION.
8. CERTIFIED FLOORING INSTALLER REQUIRED. AVAILABLE IN GEOGRAPHIC AREA: BW Hovermill - Gary Heath or Luke Patton: 410-631-2880, gheath@bwhovermill.com AND tpatton@bwhovermill.com OR APPROVED EQUAL.

Finish #	Description of Finish	Location	Manufacturer	Model/Color Number	Comments
B#1	BASE #1	THROUGHOUT EXCEPT AT SHOWERS	JOHNSONITE BY TARKETT OR APPROVED EQUAL	STYLE: MILLWORK RESILIENT WALL BASE PROFILE: SILHOUETTE 4" PRODUCT NUMBER: MW-08-J COLOR: 08 ICICLE	CONTRACTOR TO PROVIDE SAMPLES FOR APPROVAL AS SUBMITTAL
SV#1	SHEET VINYL #1	RESIDENT BATHROOMS	ALTRO OR APPROVED EQUAL	STYLE NAME: ALTRO WOOD STYLE NUMBER: WOOD SESSILE OAK COLOR: SESSILE OAK - WSA2027	TRANSITION TO BE LEVELED AND SMOOTH TO ALL OTHER FLOORING MATERIALS
SV#2	SHEET VINYL #2	RESIDENT SHOWERS	ALTRO OR APPROVED EQUAL	STYLE NAME: ALTRO AQUARIUS COLOR: LIGHTHOUSE - PX2001	TRANSITION TO BE LEVELED AND SMOOTH TO ALL OTHER FLOORING MATERIALS. INSTALLED WITH PENCIL COVE DETAIL ROLLED UP WALL BEHIND TEGULIS PANEL. DETAILING FOR WET AREAS: https://www.altro.com/getmedia/89e297f2-365d-4797-b8db-fe9d805f9a3b/DETAILING_WET-AREAS.pdf?ext=.pdf PENCIL COVER DETAIL FOR ALTRO AQUARIUS AT SHOWER: https://www.altro.com/getmedia/74f0d650-633e-459e-afb6-3132cc2a9788/Detail-Diagrams_Pencil-cove-detail-diagram.pdf TRENCH DRAIN - "CLAMPING DRAIN" REQUIRED: https://www.altro.com/us/accessories/easy-drains - OR APPROVED EQUAL.
E2	GRAB BAR E2	RESIDENT BATHROOMS	PONTE GIULIO OR APPROVED EQUAL	MANUFACTURER: PONTE GIULIO PRODUCT: HUG FOLDING GRAB BAR 33" PRODUCT NUMBER: ARM FINISH / COLOR: C1 CHROME FLANGE FINISH / COLOR: C1 CHROME ACCESSORY: TOILET PAPER HOLDER ACCESSORY PRODUCT NUMBER: F18AGS01N2 ACCESSORY FINISH / COLOR: C1 CHROME MATERIAL: STAINLESS STEEL	DROP DOWN GRAB BARS WITH TOILET PAPER HOLDER ACCESSORY AT TOILET
E3	GRAB BAR E3	RESIDENT BATHROOMS	DELTA OR APPROVED EQUAL	MANUFACTURER: DELTA PRODUCT: 18" CONTEMPORARY ADA GRAB BAR IN STAINLESS NUMBER: 41818-SS-R FINISH / COLOR: STAINLESS STEEL	SHOWER - 18" VERTICAL

E4	GRAB BAR E4	RESIDENT BATHROOMS	DELTA OR APPROVED EQUAL	MANUFACTURER: DELTA PRODUCT: 42" CONTEMPORARY DECORATIVE ADA GRAB BAR IN STAINLESS NUMBER: 41842-SS-R FINISH / COLOR: STAINLESS STEEL FOR TOILET LOCATION IN STUDIO BATHROOMS: MANUFACTURER: PONTE GUILO PRODUCT: TOILET PAPER HOLDER NUMBER: TPHCI001N2 MATERIAL: STAINLESS STEEL INSTALLATION: HORIZONTAL BELOW 42" GRAB BAR.	SHOWER / NEXT TO TOILET IN STUDIO BATHROOMS - 42" HORIZONTAL
E5	GRAB BAR E5	RESIDENT BATHROOMS	DELTA OR APPROVED EQUAL	MANUFACTURER: DELTA PRODUCT: 24" GRAB BAR CONTEMPORARY ADA IN STAINLESS NUMBER: 41824-SS-R FINISH / COLOR: STAINLESS STEEL	SHOWER - 24" HORIZONTAL
E6	TOWEL BAR (GRAB BAR STRENGTH) E6	RESIDENT BATHROOMS	DELTA OR APPROVED EQUAL	MANUFACTURER: DELTA PRODUCT: 36" GRAB BAR CONTEMPORARY ADA IN STAINLESS NUMBER: 41836-SS-R FINISH / COLOR: STAINLESS STEEL	TOWEL BAR - 36" HORIZONTAL
P#1	PAINT #1	THROUGHOUT	SHERWIN WILLIAMS OR APPROVED EQUAL	COLOR: SW 7551 GREEK VILLA	FLAT, SATIN/EGGSHELL, OR SEMI-GLOSS FINISH BASED ON SURFACE AS INDICATED ABOVE | NO VOC
WCP#1	WALL COVERING PANEL #1	SHOWER / BATHROOM WALL PANELS INCLUDING WAINSCOT FOR ALL WALLS OTHER THAN THE WET WALL.	ALTRO OR APPROVED EQUAL	STYLE NAME: ALTRO TEGULIS STYLE PATTERN: HEXAGON COLOR: SPA - 232	SHOWER ENCLOSURE. REFER TO INSTALLATION INSTRUCTIONS FOR PROPER INSTALL METHOD. ALTRO TEGULIS INSTALLATION GUIDE: https://www.altro.com/us/technical-documents/altro-tegulis-installation-guide. PAINTING TO BE COMPLETED PRIOR TO PANEL INSTALLATION AND SEALANT APPLICATION. ONCE ALL PANELS AND JOINTS ARE INSTALLED, REMOVE PROTECTIVE FILM AND CLEAN ALL SURFACES DOWN WITH ANTISTATIC SOLUTION OR ANTISTATIC WIPES.

HOUSING AUTHORITY OF THE CITY OF FROSTBURG BATHROOM RENOVATION - FINISH SCHEDULE

ROOM NAME & NUMBER	FLOOR	BASE	CORNER GUARDS	WALLS	CEILING	DOORS	TRIM	COUNTERTOPS & CASEWORK	GRAB BARS / TOWEL BARS	COMMENTS
RESIDENT BATHROOM (ALL)	SV#1 / SV#2	B#1 / SV #2 (PENCIL COVE DETAIL BEHIND TEGULIS EDGE)	N/A	P#1 / WP#1 / WP#2	P#1	P#1	P#1	SEE SECTION 22 40 00 PLUMBING FIXTURES FOR VANITIES / MIRROR / SHELF CABINET. CULTURE MARBLE INSERTS ON WOOD SHELVES: COUNTERTEK'S MARBLUX CULTURED MARBLE OR APPROVED EQUAL.	E2, E3, E4, E5, E6	